



## **Installation Instructions for Roof-Top Rail Mount Tie-Down Kits FBC 6<sup>th</sup> Edition (2017)**

### Kit Numbers

FL14CUTD6KR (Steel Tie Down Clips)  
FL14CUTD8KR (Steel Tie Down Clips)  
FL14CUTDA6KR (Aluminum Tie Down Clips)  
FL14CUTDA8KR (Aluminum Tie Down Clips)

- 1) Carefully review the included installation drawings before proceeding to anchor the condensing unit. If installing steel tie-down clips, please refer to the Mechanical Unit Steel Tie-Down Clip engineering drawing dated 8/16/2017. If installing aluminum tie-down clips, please refer to the Mechanical Unit Aluminum Tie-Down Clip engineering drawing dated 8/16/2017. The tie-down kits must be installed per the included installation drawings and the following instructions to maintain certification of the tie-down method.
- 2) Center the condensing unit on the aluminum stand I-beam/rails built with the minimum dimensions as illustrated in the included installation drawings. Use the appropriate drawing for the condensing unit being installed.
- 3) Using the bottom part of the tie down clip to rest on the I-beam/rail, attach the four (4) tie-down clips included in the kit with the appropriate quantity of #10 stainless steel 410 self-drilling screws. For 6" tie-down clips, use four (4) #10 stainless steel 410 self-drilling screws per each tie-down clip. For 8" tie-down clips, use eight (8) #10 stainless steel 410 self-drilling screws per each tie-down clip.
- 4) Drill a ¼" hole into the I-beam/rail flange to accommodate the ¼" stainless steel bolt 410. Insert a 1" OD stainless steel washer thru the bolt and slide the bolt with the washer inserted through the tie-down and I-beam/rail flange. Place a second 1" OD stainless steel washer at the end of the bolt and tighten the nut onto the bolt.



## **Installation Instructions for Roof-Top Rail Mount Tie-Down Kits FBC 6<sup>th</sup> Edition (2017)**

### Kit Numbers

FL14CUTD10KR (Steel Tie Down Clips)  
FL14CUTD12KR (Steel Tie Down Clips)  
FL14CUTDA10KR (Aluminum Tie Down Clips)  
FL14CUTDA12KR (Aluminum Tie Down Clips)

- 1) Carefully review the included installation drawings before proceeding to anchor the condensing unit. If installing steel tie-down clips, please refer to the Mechanical Unit Steel Tie-Down Clip engineering drawing dated 8/16/2017. If installing aluminum tie-down clips, please refer to the Mechanical Unit Aluminum Tie-Down Clip engineering drawing dated 8/16/2017. The tie-down kits must be installed per the included installation drawings and the following instructions to maintain certification of the tie-down method.
- 2) Center the condensing unit on the aluminum stand I-beam/rails built with the minimum dimensions as illustrated in the included installation drawings. Use the appropriate drawing for the condensing unit being installed.
- 3) Using the bottom part of the tie down clip to rest on the I-beam/rail, attach the four (4) tie-down clips included in the kit with the appropriate quantity of #10 stainless steel 410 self-drilling screws. For 10" tie-down, use eight (8) #10 stainless steel 410 self-drilling screws per each tie-down clip. For 12" tie-down, use eight (8) #10 stainless steel 410 self-drilling screws per each tie-down clip.
- 4) Drill a ¼" hole into the I-beam/rail flange to accommodate the ¼" stainless steel bolt 410. Insert a 1" OD stainless steel washer thru the bolt and slide the bolt with the washer inserted through the tie-down and I-beam/rail flange. Place a second 1" OD stainless steel washer at the end of the bolt and tighten the nut onto the bolt.


# MIAMI TECH, INC.

## MECHANICAL UNIT ALUMINUM TIE-DOWN CLIP: AT GRADE & ROOF-TOP MOUNTED APPLICATIONS


### ALUMINUM TIE-DOWN CLIP

#### SIDE VIEW TYP.



ALL OTHER CLIPS SIMILAR VARYING LENGTH ONLY




**1** 4" LONG CLIP  
1 N.T.S. FLATTENED




**2** 6" LONG CLIP  
1 N.T.S. FLATTENED



**3** 8" LONG CLIP  
1 N.T.S. FLATTENED



**4** 10" LONG CLIP  
1 N.T.S. FLATTENED



**5** 12" LONG CLIP  
1 N.T.S. FLATTENED

### DESIGN NOTES:

- THIS PRODUCT HAS BEEN DESIGNED IN ACCORDANCE WITH ASCE 7-10 AND THE FLORIDA BUILDING CODE SIXTH EDITION (2017) FOR USE WITHIN AND OUTSIDE THE HIGH VELOCITY HURRICANE ZONE AS INDICATED IN THE ACCOMPANYING DESIGN SCHEDULES. THE DESIGN CRITERIA USED TO CALCULATE THE ALLOWABLE ROOF-TOP HEIGHTS CONSIDERS FBC SECTION 1609.8 FOR NON-HVHZ AND SECTION 1620.6 FOR HVHZ ( $GC_{\text{Lateral}}=1.90$  WITHIN THE HVHZ & OUTSIDE THE HVHZ,  $GC_{\text{Updrift}}=1.5$  FOR ALL LOCATIONS (CONCURRENT)).
- ALL OTHER DESIGN VARIABLES ARE IN ACCORDANCE WITH ASCE 7-10 CHAPTERS 26 & 29.
- THE HEIGHTS LISTED IN THE DESIGN SCHEDULES REPRESENT THE ALLOWABLE HEIGHT OF THE BUILDING.
- THIS PRODUCT APPROVAL ALLOWS FOR EACH UNIT TO BE INSTALLED ON A MAXIMUM 30" TALL A/C STAND (CERTIFICATION BY OTHERS) ON TOP OF THE HEIGHTS LISTED IN THE DESIGN SCHEDULES.
- NO 33-1/3% INCREASE IN ALLOWABLE STRESS HAS BEEN USED IN THE DESIGN OF THIS SYSTEM.
- DESIGN IS BASED ON CLIENT PROVIDED PRODUCT AND DIE SHEETS FROM TEST REPORT PROJECT #15-6206 BY FENESTRATION TESTING LABORATORY, INC.. NO SUBSTITUTIONS WITHOUT WRITTEN APPROVAL BY THIS ENGINEER SHALL BE PERMITTED.
- ALL ALUMINUM TIE-DOWN CLIPS SHALL BE 0.080" 5052-H32 ALUMINUM WITH  $F_y=28$  KSI OR BETTER.

### GENERAL NOTES:

- THIS PRODUCT HAS BEEN DESIGNED AND SHALL BE FABRICATED IN ACCORDANCE WITH THE REQUIREMENTS OF THE FLORIDA BUILDING CODE & ASCE 7. THIS PRODUCT MAY BE USED WITHIN AND OUTSIDE THE HIGH VELOCITY HURRICANE ZONE.
- MAXIMUM & MINIMUM DIMENSIONS AND MINIMUM WEIGHT OF MECHANICAL UNIT SHALL CONFORM TO SPECIFICATIONS STATED HEREIN. ALL MECHANICAL SPECIFICATIONS (CLEAR SPACE, TONNAGE, ETC.) SHALL BE AS PER MANUFACTURER RECOMMENDATIONS AND ARE THE EXPRESS RESPONSIBILITY OF THE CONTRACTOR.
- FASTENERS TO BE #10 X 3/4" OR GREATER STAINLESS STEEL 410 UNLESS NOTED OTHERWISE. ANCHORS REFERRED TO HEREIN SHALL BE ELCO BRAND, STAINLESS STEEL ONLY, INSTALLED TO 3000 PSI MIN CONCRETE. SEE ANCHOR TO HOST SCHEDULE FOR ANCHOR REQUIREMENTS. ALL FASTENERS SHALL HAVE APPROPRIATE CORROSION PROTECTION TO PREVENT ELECTROLYSIS.
- ALL CONCRETE SPECIFIED HEREIN IS NOT PART OF THIS CERTIFICATION. AS A MINIMUM, ALL CONCRETE SHALL BE STRUCTURAL CONCRETE 4" MIN. THICK AND SHALL HAVE MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI, UNLESS NOTED OTHERWISE.
- THE CONTRACTOR IS RESPONSIBLE TO INSULATE ALL MEMBERS FROM DISSIMILAR MATERIALS TO PREVENT ELECTROLYSIS.
- ELECTRICAL GROUND, WHEN REQUIRED, TO BE DESIGNED & INSTALLED BY OTHERS.
- THE ADEQUACY OF ANY EXISTING STRUCTURE TO WITHSTAND SUPERIMPOSED LOADS SHALL BE VERIFIED BY THE ONSITE DESIGN PROFESSIONAL AND IS NOT INCLUDED IN THIS CERTIFICATION. EXCEPT AS EXPRESSLY PROVIDED HEREIN, NO ADDITIONAL CERTIFICATIONS OR AFFIRMATIONS ARE INTENDED.
- THE SYSTEM DETAILED HEREIN IS GENERIC AND DOES NOT PROVIDE INFORMATION FOR A SPECIFIC SITE. FOR SITE CONDITIONS DIFFERENT FROM THE CONDITIONS DETAILED HEREIN, A LICENSED ENGINEER OR REGISTERED ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE IN CONJUNCTION WITH THIS DOCUMENT.
- WATER-TIGHTNESS OF EXISTING HOST SUBSTRATE SHALL BE THE FULL RESPONSIBILITY OF THE INSTALLING CONTRACTOR. CONTRACTOR SHALL ENSURE THAT ANY REMOVED OR ALTERED WATERPROOFING MEMBRANE IS RESTORED AFTER FABRICATION AND INSTALLATION OF STRUCTURE PROPOSED HEREIN. THIS ENGINEER SHALL NOT BE RESPONSIBLE FOR ANY WATERPROOFING OR LEAKAGE ISSUES WHICH MAY OCCUR AS WATER-TIGHTNESS SHALL BE THE FULL RESPONSIBILITY OF THE INSTALLING CONTRACTOR.
- FOR AN EXPLANATION OF EXPOSURE AND RISK CATEGORIES THAT ACCOMPANY THE WIND SPEEDS USED IN THIS APPROVAL, SEE SECTION 26.7.3 OF ASCE 7-10.

FRANK L. BENNARDO, P.E.  
PE# 0046549

FRANK L. BENNARDO  
08/16/2017  
No PE0046549


STATE OF FLORIDA  
ENGINEERING EXPRESS  
CORPORATE OFFICE:  
160 SW 12th AVE, SUITE 106  
DEERFIELD BEACH, FL 33442  
P: (954) 354-0660 F: (954) 354-0449  
E: HELLO@ENGINEERINGEXPRESS.COM  
ENGINEERINGEXPRESS.COM  
CERT OF AUTH #9885

MIAMI TECH, INC.  
3611 NW 74TH ST  
MIAMI, FL  
(305) 693-7054  
MIAMI TECH CUTD TIE-DOWN CLIP CERTIFICATIONS  
FBC 6TH EDITION (2017) PRODUCT APPROVAL FL#19731.1


REMARKS	DRWN	CHKD	DATE
INIT ISSUE	LAO	TSB	02/05/16
REV (ADD DETAILS)	RWN	FLB	07/14/16
REV 2017 FBC UPDATE	LAO	FLB	08/15/17

THIS DOCUMENT IS THE PROPERTY OF ENGINEERING EXPRESS AND SHALL NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN CONSENT OF ENGINEERING EXPRESS. ALTERATIONS, ADDITIONS, OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE OUR CERTIFICATION.

COPYRIGHT ENGINEERING EXPRESS  
15-2786a  
SCALE: N.T.S.




**C1 CONNECTION TYPE C1**  
 1"x6" CLIP - UTILIZE (1) AT EACH CORNER FOR A TOTAL OF (4) PER UNIT  
 NOTE: ALSO APPLICABLE FOR CLIP 4" LONG




**C3 CONNECTION TYPE C3**  
 1"x12" CLIP - UTILIZE (1) AT EACH CORNER FOR A TOTAL OF (4) PER UNIT  
 NOTE: ALSO APPLICABLE FOR CLIPS 8" & 10" LONG


\*NOTE: SEE ANCHOR TO HOST SCHEDULE FOR ALL EDGE DISTANCE TO ANCHOR SPACING LIMITATIONS. SEE PAGE 4.



**C2 CONNECTION TYPE C2**  
 1"x6" CLIP - UTILIZE (2) AT EACH CORNER FOR A TOTAL OF (8) PER UNIT  
 NOTE: ALSO APPLICABLE FOR CLIP 4" LONG



**C4 CONNECTION TYPE C4**  
 1"x12" CLIP - UTILIZE (2) AT EACH CORNER FOR A TOTAL OF (8) PER UNIT  
 NOTE: ALSO APPLICABLE FOR CLIPS 8" & 10" LONG



**ENGINEERING EXPRESS**  
 CORPORATE OFFICE:  
 160 SW 12th AVE, SUITE 106  
 DEERFIELD BEACH, FL 33442  
 P: (954) 354-0660 F: (954) 354-0443  
 E: HELLO@ENGINEERINGEXPRESS.COM  
 CERT OF AUTH #9885


**MIAMI TECH, INC.**  
 3611 NW 74TH ST  
 MIAMI, FL  
 (305) 693-7054  
 MIAMI TECH CUTD TIE-DOWN CLIP CERTIFICATIONS  
 MIAMI TECH EDITION (2017) PRODUCT APPROVAL FL#19731.1

REMARKS	DRWN	CHKD	DATE
INIT ISSUE	LAO	TSB	02/05/16
REV (ADD DETAILS)	RWN	FLB	07/14/16
REV 2017 FBC UPDATE	LAO	FLB	08/14/17


THIS DOCUMENT IS THE PROPERTY OF ENGINEERING EXPRESS AND SHALL NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN CONSENT OF ENGINEERING EXPRESS. ALTERATIONS, ADDITIONS, OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE OUR CERTIFICATION.

15-2786a  
 SCALE: N.T.S.  
 2


**ATTACHMENT TO STAND**




**C1 CONNECTION TYPE C1**  
 1"x6" CLIP - UTILIZE (1) AT EACH CORNER FOR A TOTAL OF (4) PER UNIT  
 NOTE: ALSO APPLICABLE FOR CLIP 4" LONG



**C3 CONNECTION TYPE C3**  
 1"x12" CLIP - UTILIZE (1) AT EACH CORNER FOR A TOTAL OF (4) PER UNIT  
 NOTE: ALSO APPLICABLE FOR CLIPS 8" & 10" LONG




**A ALTERNATE CLIP TO STAND DETAIL**  
 SCALE: N.T.S.



**C2 CONNECTION TYPE C2**  
 1"x6" CLIP - UTILIZE (2) AT EACH CORNER FOR A TOTAL OF (8) PER UNIT  
 NOTE: ALSO APPLICABLE FOR CLIP 4" LONG

\*NOTE: SEE ANCHOR TO HOST SCHEDULE FOR ALL EDGE DISTANCE TO ANCHOR SPACING LIMITATIONS. SEE PAGE 4.



**C4 CONNECTION TYPE C4**  
 1"x12" CLIP - UTILIZE (2) AT EACH CORNER FOR A TOTAL OF (8) PER UNIT  
 NOTE: ALSO APPLICABLE FOR CLIPS 8" & 10" LONG

FRANK L. BENNARDO, P.E.  
 PE# 0046549  
 08/16/2017  
 No PE0046549

STATE OF FLORIDA  
 PROFESSIONAL ENGINEERING  
**ENGINEERING EXPRESS**  
 CORPORATE OFFICE:  
 160 SW 12th AVE, SUITE 200  
 DEERFIELD BEACH, FL 33442  
 P: (954) 354-0660 F: (954) 354-0443  
 E: HELLO@ENGINEERINGEXPRESS.COM  
 ENGINEERINGEXPRESS.COM  
 CERT OF AUTH #9885

**MIAMI TECH, INC.**  
 3611 NW 74TH ST  
 MIAMI, FL  
 (305) 693-7054  
 MIAMI TECH CUTD TIE-DOWN CLIP CERTIFICATIONS  
 PRODUCT APPROVAL FL#19731.1

REMARKS	DRWN	CHKD	DATE
INIT ISSUE	LAO	TSB	02/05/16
REV (ADD DETAILS)	RWN	FLB	07/14/16
REV 2017 FBC UPDATE	LAO	FLB	08/14/17


THIS DOCUMENT IS THE PROPERTY OF ENGINEERING EXPRESS AND SHALL NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN CONSENT OF ENGINEERING EXPRESS. ALTERATIONS, ADDITIONS, OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE OUR CERTIFICATION.

15-2786a  
 SCALE: N.T.S.  
 3

V:\Projects\15-2786 Miami Tech CUTD Tie-Down Clip Certifications\WP\2017 FBC Update\15-2786-Dwg-FL-19731.1.dwg  
 08/16/2017 - 2:08pm  
 zachr


**ALUMINUM TIE-DOWN CLIP**

08/16/2017 - 2:08pm zachr V:\Projects\15-2786 Miami Tech CUDT Tie-Down Clip Certifications\WP\2017 FBC Update\15-2786-FBC-Dwg-FL-19731-1.dwg




**1** 1" CLIP ISOMETRIC DETAIL  
 4 N.T.S. ISOMETRIC

MECHANICAL UNIT BY OTHERS. ALUMINUM HOUSING UNITS SHALL BE 6063-T6 MIN. ALUMINUM SHEET WITH  $F_{ty}=30$  KSI, 0.125" MIN. THICKNESS, STEEL HOUSING UNITS SHALL BE ASTM A653  $F_y=33$ KSI MIN. STEEL, GRADE 33, 22GA MIN. ( $t=0.0299$ ").



**2** 1" TIE-DOWN CLIP ANCHOR DETAIL  
 4 3" = 1'-0" DETAIL


CLIP IS DESIGNED FOR FULL CONTACT WITH THE BASE OF EACH MECHANICAL UNIT, TYP.



**ANCHOR TO HOST SCHEDULE:**

SUBSTRATE	DESCRIPTION
CONCRETE: (4" THICK MIN, 3000 PSI MIN.)	(1)-1/4"Ø STAINLESS STEEL 410 ELCO ULTRACON, 1 3/4" FULL EMBED TO CONCRETE, 2 1/2" MIN. EDGE DISTANCE, 3" MIN. SPACING TO ANY ADJACENT ANCHOR.
ALUMINUM: (0.125" MIN. THICK, 6061-T6 MIN. ALUMINUM)	(1)-#14 SAE STAINLESS STEEL BOLT 410 WITH NUT AND WASHER TOP & BOTTOM SS OD 1", 1/2" MINIMUM EDGE DISTANCE TO METAL EDGE
STEEL: (0.125" MIN. THICK, 50 KSI MIN. STEEL)	(1)-#14 SAE STAINLESS STEEL BOLT 410 WITH NUT AND WASHER TOP & BOTTOM SS OD 1", 1/2" MINIMUM EDGE DISTANCE TO METAL EDGE

1. EMBEDMENT AND EDGE DISTANCE EXCLUDES FINISHES, IF APPLICABLE.
2. ENSURE MINIMUM EDGE DISTANCE AS NOTED IN ANCHOR SCHEDULE.
3. ENSURE MINIMUM SPACING TO ANY ADJACENT ANCHORS.
4. SEE DETAILS ON SHEET 4 FOR ANCHORS ATTACHING TO MECHANICAL UNIT.
5. PROTECT ALL METALS FROM DISSIMILAR METALS GENERAL NOTE #5



**3** ALTERNATE (8) CLIP DETAIL  
 4 N.T.S. PLAN VIEW

THIS DETAIL MAY BE USED AS AN ALTERNATE GEOMETRIC PATTERN FOR ALL CONNECTION TYPES THAT UTILIZE (2) CLIPS AT EACH CORNER FOR A TOTAL OF (8) CLIPS PER UNIT.

FRANK L. BENNARDO, P.E.  
 PE# 0046549  
 LICENSED PROFESSIONAL ENGINEER  
 STATE OF FLORIDA  
 No PE0046549  
 08/16/2017

**ENGINEERING EXPRESS**  
 CORPORATE OFFICE:  
 160 SW 12th AVE, SUITE 1068  
 DEERFIELD BEACH, FL 33442  
 P: (954) 354-0660 F: (954) 354-0443  
 E: HELLO@ENGINEERINGEXPRESS.COM  
 ENGINEERINGEXPRESS.COM  
 CERT OF AUTH #9885

**MIAMI TECH, INC.**  
 3611 NW 74TH ST  
 MIAMI, FL  
 (305) 693-7054

MIAMI TECH CUDT TIE-DOWN CLIP CERTIFICATIONS  
 MIAMI TECH CUDT TIE-DOWN CLIP CERTIFICATIONS  
 FBC 6TH EDITION (2017) PRODUCT APPROVAL FL#19731.1

REMARKS	DRWN	CHKD	DATE
INIT ISSUE	LAO	TSB	02/05/16
REV (ADD DETAILS)	RWN	FLB	07/14/16
REV 2017 FBC UPDATE	LAO	FLB	08/14/17

THIS DOCUMENT IS THE PROPERTY OF ENGINEERING EXPRESS AND SHALL NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN CONSENT OF ENGINEERING EXPRESS. ALTERATIONS, ADDITIONS, OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE OUR CERTIFICATION.

15-2786a  
 SCALE: N.T.S.  
 4

**TABLE 1 PERMISSIBLE INSTALLATION HEIGHTS: Vult=175 MPH, EXPOSURE C**

(FOR USE WITH A RISK CATEGORY II STRUCTURE IN THE HIGH VELOCITY HURRICANE ZONE (HVHZ)\*)  
RISK CATEGORY II IS PER ASCE 7-10

MAXIMUM SURFACE AREA OF UNIT'S LARGEST FACE	UNIT HEIGHT	UNIT WIDTH	ALLOWABLE ROOF-TOP HEIGHT (H) TIE-DOWN CONFIGURATION TYPE			
			C1	C2	C3	C4
6 FT <sup>2</sup>	29" MAX	15" MIN	N/A	H ≤ 40 FT	N/A	H ≤ 40 FT
9 FT <sup>2</sup>	36" MAX	27" MIN	N/A	H ≤ 15 FT	N/A	H ≤ 15 FT
4 FT <sup>2</sup>	48" MAX	36" MIN	AT GRADE	H ≤ 200 FT	AT GRADE	H ≤ 200 FT
6 FT <sup>2</sup>			N/A	H ≤ 140 FT	N/A	H ≤ 140 FT
9 FT <sup>2</sup>			N/A	H ≤ 15 FT	N/A	H ≤ 15 FT
12 FT <sup>2</sup>			N/A	AT GRADE	N/A	AT GRADE
16 FT <sup>2</sup>			N/A	N/A	N/A	N/A
20 FT <sup>2</sup>	60" MAX	48" MIN	N/A	N/A	N/A	N/A
25 FT <sup>2</sup>			N/A	N/A	N/A	N/A
30 FT <sup>2</sup>			N/A	N/A	N/A	N/A
36 FT <sup>2</sup>			N/A	N/A	N/A	N/A

\*THIS TABLE IS PERMISSIBLE TO BE USED WITHIN THE HVHZ WHICH CONTAINS BROWARD AND MIAMI-DADE COUNTIES. CHECK WITH LOCAL AUTHORITY HAVING JURISDICTION FOR THE APPLICABILITY OF THIS TABLE WITHIN CERTAIN FLORIDA COUNTIES.

**TABLE 2 PERMISSIBLE INSTALLATION HEIGHTS: Vult=175 MPH, EXPOSURE D**

(FOR USE WITH A RISK CATEGORY II STRUCTURE IN THE HIGH VELOCITY HURRICANE ZONE (HVHZ)\*)  
RISK CATEGORY II IS PER ASCE 7-10

MAXIMUM SURFACE AREA OF UNIT'S LARGEST FACE	UNIT HEIGHT	UNIT WIDTH	ALLOWABLE ROOF-TOP HEIGHT (H) TIE-DOWN CONFIGURATION TYPE			
			C1	C2	C3	C4
6 FT <sup>2</sup>	29" MAX	15" MIN	N/A	H ≤ 15 FT	N/A	H ≤ 15 FT
9 FT <sup>2</sup>	36" MAX	27" MIN	N/A	AT GRADE	N/A	AT GRADE
4 FT <sup>2</sup>	48" MAX	36" MIN	AT GRADE	H ≤ 200 FT	AT GRADE	H ≤ 200 FT
6 FT <sup>2</sup>			N/A	H ≤ 60 FT	N/A	H ≤ 80 FT
9 FT <sup>2</sup>			N/A	AT GRADE	N/A	AT GRADE
12 FT <sup>2</sup>			N/A	AT GRADE	N/A	AT GRADE
16 FT <sup>2</sup>			N/A	N/A	N/A	N/A
20 FT <sup>2</sup>	60" MAX	48" MIN	N/A	N/A	N/A	N/A
25 FT <sup>2</sup>			N/A	N/A	N/A	N/A
30 FT <sup>2</sup>			N/A	N/A	N/A	N/A
36 FT <sup>2</sup>			N/A	N/A	N/A	N/A

\*THIS TABLE IS PERMISSIBLE TO BE USED WITHIN THE HVHZ WHICH CONTAINS BROWARD AND MIAMI-DADE COUNTIES. CHECK WITH LOCAL AUTHORITY HAVING JURISDICTION FOR THE APPLICABILITY OF THIS TABLE WITHIN CERTAIN FLORIDA COUNTIES.

**TABLE 3 PERMISSIBLE INSTALLATION HEIGHTS: Vult=170 MPH, EXPOSURE C**

(FOR USE WITH A RISK CATEGORY II STRUCTURE\*\*) RISK CATEGORY II IS PER ASCE 7-10

MAXIMUM SURFACE AREA OF UNIT'S LARGEST FACE	UNIT HEIGHT	UNIT WIDTH	ALLOWABLE INSTALLATION ROOF HEIGHT TIE-DOWN CONFIGURATION TYPE			
			C1	C2	C3	C4
6 ft <sup>2</sup>	29 in	15 in	N/A	H ≤ 60 FT	N/A	H ≤ 60 FT
9 ft <sup>2</sup>	36 in	27 in	N/A	H ≤ 15 FT	N/A	H ≤ 15 FT
4 ft <sup>2</sup>	48 in	36 in	H ≤ 15 FT	≤ 200 FT	H ≤ 15 FT	≤ 200 FT
6 ft <sup>2</sup>	48 in	36 in	AT GRADE	≤ 180 FT	AT GRADE	≤ 200 FT
9 ft <sup>2</sup>	48 in	36 in	N/A	H ≤ 15 FT	N/A	H ≤ 15 FT
12 ft <sup>2</sup>	48 in	36 in	N/A	AT GRADE	N/A	AT GRADE
16 ft <sup>2</sup>	48 in	36 in	N/A	N/A	N/A	N/A
20 ft <sup>2</sup>	60 in	48 in	N/A	N/A	N/A	N/A
25 ft <sup>2</sup>	60 in	48 in	N/A	N/A	N/A	N/A
30 ft <sup>2</sup>	60 in	48 in	N/A	N/A	N/A	N/A
36 ft <sup>2</sup>	60 in	48 in	N/A	N/A	N/A	N/A

**TABLE 4 PERMISSIBLE INSTALLATION HEIGHTS: Vult=170 MPH, EXPOSURE D**

(FOR USE WITH A RISK CATEGORY II STRUCTURE\*\*) RISK CATEGORY II IS PER ASCE 7-10

MAXIMUM SURFACE AREA OF UNIT'S LARGEST FACE	UNIT HEIGHT	UNIT WIDTH	ALLOWABLE INSTALLATION ROOF HEIGHT TIE-DOWN CONFIGURATION TYPE			
			C1	C2	C3	C4
6 ft <sup>2</sup>	29 in	15 in	N/A	H ≤ 15 FT	N/A	H ≤ 15 FT
9 ft <sup>2</sup>	36 in	27 in	N/A	AT GRADE	N/A	AT GRADE
4 ft <sup>2</sup>	48 in	36 in	AT GRADE	≤ 200 FT	AT GRADE	≤ 200 FT
6 ft <sup>2</sup>	48 in	36 in	N/A	≤ 100 FT	N/A	≤ 100 FT
9 ft <sup>2</sup>	48 in	36 in	N/A	AT GRADE	N/A	AT GRADE
12 ft <sup>2</sup>	48 in	36 in	N/A	AT GRADE	N/A	AT GRADE
16 ft <sup>2</sup>	48 in	36 in	N/A	N/A	N/A	N/A
20 ft <sup>2</sup>	60 in	48 in	N/A	N/A	N/A	N/A
25 ft <sup>2</sup>	60 in	48 in	N/A	N/A	N/A	N/A
30 ft <sup>2</sup>	60 in	48 in	N/A	N/A	N/A	N/A
36 ft <sup>2</sup>	60 in	48 in	N/A	N/A	N/A	N/A

\*\*AS AN EXAMPLE, THESE TABLES ARE PERMISSIBLE TO BE USED WITHIN PALM BEACH COUNTY. CHECK WITH LOCAL AUTHORITY HAVING JURISDICTION FOR THE APPLICABILITY OF THESE TABLES WITHIN CERTAIN FLORIDA COUNTIES.

ALUMINUM TIE-DOWN CLIP

FRANK L. BENNARDO, P.E.  
PE# 0046549  
08/16/2017  
No PE0046549

STATE OF FLORIDA  
ENGINEERING EXPRESS  
CORPORATE OFFICE:  
160 SW 12th AVE, SUITE 3006  
DEERFIELD BEACH, FL 33442  
P: (954) 354-0660 F: (954) 354-0443  
E: HELLO@ENGINEERINGEXPRESS.COM  
ENGINEERINGEXPRESS.COM  
CERT OF AUTH #9885

MIAMI TECH, INC.  
3611 NW 74TH ST  
MIAMI, FL  
(305) 693-7054

MIAMI TECH CUTD TIE-DOWN CLIP CERTIFICATIONS  
FBC 6TH EDITION (2017) PRODUCT APPROVAL FL#19731.1

REMARKS	DRWN	CHKD	DATE
INIT ISSUE	LAO	TSB	02/05/16
REV (ADD DETAILS)	RWN	FLB	07/14/16
REV 2017 FBC UPDATE	LAO	FLB	08/14/17

THIS DOCUMENT IS THE PROPERTY OF ENGINEERING EXPRESS AND SHALL NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN CONSENT OF ENGINEERING EXPRESS. ALTERATIONS, ADDITIONS, OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE OUR CERTIFICATION.

COPYRIGHT ENGINEERING EXPRESS ©  
15-2786a  
SCALE: N.T.S.  
5

08/16/2017 - 2:06pm zachr V:\Projects\15-2786 Miami Tech CUTD Tie-Down Clip Certifications\WP\2017 FBC Update\15-2786f.Dwg-FL19731.1.dwg

**TABLE 5 PERMISSIBLE INSTALLATION HEIGHTS:  $v_{ult}=140$  MPH, EXPOSURE B**

(FOR USE WITH A RISK CATEGORY II STRUCTURE\*\*\*)  
RISK CATEGORY II IS PER ASCE 7-10

MAXIMUM SURFACE AREA OF UNIT'S LARGEST FACE	UNIT HEIGHT	UNIT WIDTH	ALLOWABLE INSTALLATION ROOF HEIGHT TIE-DOWN CONFIGURATION TYPE			
			C1	C2	C3	C4
6 ft <sup>2</sup>	29 in	15 in	H ≤ 15 FT	≤ 200 FT	H ≤ 15 FT	≤ 200 FT
9 ft <sup>2</sup>	36 in	27 in	AT GRADE	≤ 200 FT	AT GRADE	≤ 200 FT
4 ft <sup>2</sup>	48 in	36 in	≤ 200 FT	≤ 200 FT	≤ 200 FT	≤ 200 FT
6 ft <sup>2</sup>	48 in	36 in	H ≤ 40 FT	≤ 200 FT	H ≤ 60 FT	≤ 200 FT
9 ft <sup>2</sup>	48 in	36 in	AT GRADE	≤ 200 FT	AT GRADE	≤ 200 FT
12 ft <sup>2</sup>	48 in	36 in	AT GRADE	≤ 120 FT	AT GRADE	≤ 120 FT
16 ft <sup>2</sup>	48 in	36 in	N/A	H ≤ 40 FT	N/A	H ≤ 40 FT
20 ft <sup>2</sup>	60 in	48 in	N/A	H ≤ 15 FT	N/A	H ≤ 15 FT
25 ft <sup>2</sup>	60 in	48 in	N/A	AT GRADE	N/A	AT GRADE
30 ft <sup>2</sup>	60 in	48 in	N/A	AT GRADE	N/A	AT GRADE
36 ft <sup>2</sup>	60 in	48 in	N/A	N/A	N/A	N/A

**TABLE 6 PERMISSIBLE INSTALLATION HEIGHTS:  $v_{ult}=140$  MPH, EXPOSURE C**

(FOR USE WITH A RISK CATEGORY II STRUCTURE\*\*\*)  
RISK CATEGORY II IS PER ASCE 7-10

MAXIMUM SURFACE AREA OF UNIT'S LARGEST FACE	UNIT HEIGHT	UNIT WIDTH	ALLOWABLE INSTALLATION ROOF HEIGHT TIE-DOWN CONFIGURATION TYPE			
			C1	C2	C3	C4
6 ft <sup>2</sup>	29 in	15 in	AT GRADE	≤ 200 FT	AT GRADE	≤ 200 FT
9 ft <sup>2</sup>	36 in	27 in	N/A	≤ 160 FT	AT GRADE	≤ 160 FT
4 ft <sup>2</sup>	48 in	36 in	≤ 100 FT	≤ 200 FT	≤ 100 FT	≤ 200 FT
6 ft <sup>2</sup>	48 in	36 in	AT GRADE	≤ 200 FT	AT GRADE	≤ 200 FT
9 ft <sup>2</sup>	48 in	36 in	AT GRADE	≤ 180 FT	AT GRADE	≤ 180 FT
12 ft <sup>2</sup>	48 in	36 in	N/A	H ≤ 40 FT	N/A	H ≤ 40 FT
16 ft <sup>2</sup>	48 in	36 in	N/A	AT GRADE	N/A	AT GRADE
20 ft <sup>2</sup>	60 in	48 in	N/A	AT GRADE	N/A	AT GRADE
25 ft <sup>2</sup>	60 in	48 in	N/A	N/A	N/A	N/A
30 ft <sup>2</sup>	60 in	48 in	N/A	N/A	N/A	N/A
36 ft <sup>2</sup>	60 in	48 in	N/A	N/A	N/A	N/A

**TABLE 7 PERMISSIBLE INSTALLATION HEIGHTS:  $v_{ult}=140$  MPH, EXPOSURE D**

(FOR USE WITH A RISK CATEGORY II STRUCTURE\*\*\*)  
RISK CATEGORY II IS PER ASCE 7-10

MAXIMUM SURFACE AREA OF UNIT'S LARGEST FACE	UNIT HEIGHT	UNIT WIDTH	ALLOWABLE INSTALLATION ROOF HEIGHT TIE-DOWN CONFIGURATION TYPE			
			C1	C2	C3	C4
6 ft <sup>2</sup>	29 in	15 in	N/A	≤ 200 FT	N/A	≤ 200 FT
9 ft <sup>2</sup>	36 in	27 in	N/A	≤ 80 FT	N/A	≤ 80 FT
4 ft <sup>2</sup>	48 in	36 in	H ≤ 40 FT	≤ 200 FT	H ≤ 40 FT	≤ 200 FT
6 ft <sup>2</sup>	48 in	36 in	AT GRADE	≤ 200 FT	AT GRADE	≤ 200 FT
9 ft <sup>2</sup>	48 in	36 in	N/A	≤ 80 FT	N/A	≤ 100 FT
12 ft <sup>2</sup>	48 in	36 in	N/A	H ≤ 15 FT	N/A	H ≤ 15 FT
16 ft <sup>2</sup>	48 in	36 in	N/A	AT GRADE	N/A	AT GRADE
20 ft <sup>2</sup>	60 in	48 in	N/A	N/A	N/A	N/A
25 ft <sup>2</sup>	60 in	48 in	N/A	N/A	N/A	N/A
30 ft <sup>2</sup>	60 in	48 in	N/A	N/A	N/A	N/A
36 ft <sup>2</sup>	60 in	48 in	N/A	N/A	N/A	N/A

\*\*\*AS AN EXAMPLE, THESE TABLES ARE PERMISSIBLE TO BE USED WITHIN BREVARD COUNTY. CHECK WITH LOCAL AUTHORITY HAVING JURISDICTION FOR THE APPLICABILITY OF THIS TABLE WITHIN CERTAIN FLORIDA COUNTIES.

FRANK L. BENNARDO, P.E.  
PE# 0046549

08/16/2017

No PE0046549

STATE OF FLORIDA

ENGINEERING EXPRESS®  
CORPORATE OFFICE:  
160 SW 12th AVE, SUITE 306  
DEERFIELD BEACH, FL 33442  
P: (954) 354-0660 F: (954) 354-0443  
E: HELLO@ENGINEERINGEXPRESS.COM  
ENGINEERINGEXPRESS.COM  
CERT OF AUTH #9885

**MIAMI TECH, INC.**  
3611 NW 74TH ST  
MIAMI, FL  
(305) 693-7054

MIAMI TECH CUTD TIE-DOWN CLIP CERTIFICATIONS  
FBC 6TH EDITION (2017) PRODUCT APPROVAL FL#19731.1

REMARKS	DRWN	CHKD	DATE
INIT ISSUE	LAO	TSB	02/05/16
REV (ADD DETAILS)	RWN	FLB	07/14/16
REV 2017 FBC UPDATE	LAO	FLB	08/14/17

THIS DOCUMENT IS THE PROPERTY OF ENGINEERING EXPRESS AND SHALL NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN CONSENT OF ENGINEERING EXPRESS. ALTERATIONS, ADDITIONS, OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE OUR CERTIFICATION.

COPYRIGHT ENGINEERING EXPRESS®

15-2786a

SCALE: N.T.S.

ALUMINUM TIE-DOWN CLIP

V:\Projects\15-2786 Miami Tech CUTD Tie-Down Clip Certifications\WP\2017 FBC Update\15-2786-Dwg-FL19731.1.dwg

zachr

08/16/2017 - 2:08pm